

QUESTIONS AND ANSWERS

RFP 17/18-003

SURVEILLANCE CAMERA SYSTEMS

SUBMITTALS DUE NO LATER THAN MAY 29, 2018 @ 2:00 PM

To clarify, no bid bond is required; however both payment and performance bonds are required.

CORRECT

What is the expected minimum storage retention time? (30 days, 60 days, 90 days, etc. **30 DAYS**

How many frames per second are you looking to capture at a minimum? **SPECS CALL FOR 30FPS**

Is this an item that we should just include our recommendation with an explanation for why we are recommending what we are? **YOU CAN**

Are you looking to record 24 hours per day – 7 days per week or on motion events only? **NO- 24/7**

WITH INTELLIGENCE TO BE ABLE TO FLAG MOTION EVENTS

Are you looking to have a dedicated workstation and monitor (s) located at each site? **NO**

Are these to be provided by the security contractor? **NO**

Or are you looking for a system that allows you to log into the VMS application from any computer on the same network with just an internet browser and authorized credentials to use the software? **YES**

Will the district, for the sake of competitive purposes, allow a base bid that includes the cameras specified with a value engineered option for what we recommend to be a better, more cost effective and forensically useful solution? **YES**

Should an IDF be maxed out and additional network ports be required, who is responsible for the provision and installation of the additional switch, patch panel, UPS, wall mounted enclosure, etc?

DISTRICT

Should we all simply include a line item for contingency needs in the amount of say \$15,000 to cover this equipment if during the course of the project it is determined that this additional equipment will be required? **NO**

The Bill of Materials in the RFP lists camera mounts for only 15 cameras at each site. What about the other 7 cameras? **THIS WILL BE AN ADDENDUM**

Is the district looking to have the security contractor certify the CAT6 cabling and connections? **YES**

It looks like Multimode fiber cabling is used to connect each IDF in the field back to the MDF in the Principal's office. Is it safe to assume that each remote IDF is definitely connected via fiber currently? **YES**

Can you verify that Multimode fiber is used and that the connections are SC connectors? **NO**

Is the security contractor required to do any fiber work? **NO**

What is the estimated project schedule? **TBD**

Are you looking for completion over the summer when school is unoccupied? **IDEALLY, YES**

Are standard hours all that we are to include in our bid submittals or should we include 2nd shift labor costs and/or weekend labor rates? **THAT WOULD BE FOR EACH VENDOR TO DETERMINE.**

Can you verify the Power Over Ethernet power budget of your existing Juniper Networks switches? **REFER TO PAGE 13, B-GENERAL SPECIFICATIONS**

Do these switches offer POE+ power for cameras that include built-in heaters or for PTZ cameras? **REFER TO PAGE 13, 1 (TOP OF PAGE)**

The NVR's are specified to include 36TB of hard drive space. Is this in a RAID configuration? **YES**

Is the true intention to have all 22 cameras at each site record and store the video locally at each school with the district security control room able to call up any camera from any school or multiple cameras from multiple schools at the same time? **YES (REFER TO PAGE 1-PROJECT BACKGROUND)**

Or is the district planning to stream all cameras via the WLAN back to the district security control room allowing for a programmed view of cameras to be displayed on existing monitors? **NO**

Are there any notifications or alarms that the district would like to monitor such as: camera going offline, NVR not recording, UPS in an alarm state, hard drive failure, etc. **YES**

Should our bid submitted pricing include sales-use tax? **NO**

Are you looking to have the ability to integrate the VMS system with any of your existing systems? Such as access control, HVAC, fire alarm, intrusion detection, etc. **NO**

Are the security contractors able to utilize any existing raceways or conduits? **YES, IF SPACE IS AVAILABLE.** Are we responsible for all required conduits, pull boxes, etc. **YES, (REFER TO PAGE 1-PROJECT BACKGROUND)**

Can multiple schools be installed at the same time or are you looking to begin and complete one school before the next one begins? **MULTIPLE SCHOOLS CAN BE INSTALLED AT THE SAME TIME**

Will you require the ability to review live and/or recorded video from a mobile device (smartphone or tablet – IOS or Android)? **NOT REQUIRED**

Will you require outdoor rated cabling (such as AquaSeal) for the outdoor cabling runs? **NO**

6.1.1A – The NVR shall be compatible with existing IP security cameras. – Can you provide a list of existing cameras that would be required to reside on the new VMS? **ACTI & HIKVISION**

6.1.1D – The NVR shall be installed with 36TB of HDD space or greater.

- a. Is this storage calculated as RAW or Usable? **USABLE** If usable, what RAID is being utilized? **RAID (DEPENDING ON SOLUTION PROVIDED)**
- b. Is this storage per site or in total for the district? **PER SITE**
- c. What parameters were used to calculate this storage requirement? **UNKNOWN**

6.1.1G - The NVR shall enable centralized management of all system components using a single administration application located anywhere on or off the network.

- c. Are you looking for mobile and web access or just management (not viewing) capabilities from anywhere? **YES**

If the built in IR meets the distance requirements, does it still need to meet the 15 pieces of built-in IR LED illuminator or greater, requirement? **NO**

For camera locations utilizing MPR buildings, should the installer assume crawl space is available to route cables through the MPR ceiling space or should a conduit run be included to route the cables outside of the building to the new camera locations? **YES**

For Adelanto Elem, will existing conduit path be available to utilize for the new cameras? **IF SPACE IS AVAILABLE**

For Adelanto Elem, will the backbone conduit pathways be available to use for new camera cables? **IF ROOM IS AVAILABLE**

For Adelanto Elem, one of the IDF cabinets is not structurally secure. Please confirm that the SD will repair this prior to the installation. **YES**

Is a bid bond required? **NO**

Is this a prevailing wage project? **YES**

We did not hear back about the demo we did last week so I am not sure the district has decided how they want to proceed with VMS and Hardware. Do we include spec sheets in our proposal for equipment and VMS we intend to install or is a formal request required? **YES, INCLUDE INFORMATION IN YOUR PROPOSAL**